

ADDENDUM #1

Date: April 11, 2018

This Addendum applicable to work designated herein shall be understood to be and is an Addendum and as such shall be part of and included in the Contract.

To all bidders for furnishing all labor and materials necessary for:

Rigby High School Bleacher Addition School District #251 Rigby, Idaho

Failure to acknowledge receipt of this Addendum on the bid proposal form may result in rejection of your bid.

ARCHITECTURAL ITEMS

- 1. The Substantial Completion Date for this project is hereby changed to be 120 calendar days following Notice To Proceed.
- 2. Subject to Specification requirements, the following are acceptable manufacturers:

Specification 13 1250, paragraph 2.01:

- 1. Sturdisteel, Waco, TX
- 3. Drawing Sheet D1.1, Demolition Keynote 1: Contractor shall remove a portion of the existing chain link fencing as required to install new bleachers and walkways. The Owner will reconfigure existing chain link fencing and install new gates and entrances following Substantial Completion of this project.
- 4. Extend 2 x 4 stud screen wall with painted MDF on one side and .032 aluminum cap and end trim to match existing at the front of the bleacher walkway.
- 5. Saw cut and remove existing concrete slab as required to install new concrete foundations. Replace removed concrete with gravel to match existing.
- 6. Contractor will provide temporary barricades and access as required to safely accommodate patrons during home football games.

END OF ADDENDUM NO.1



Scott L. Nielson, A.A. Kevin R. Bodily, A.A. James H. Wyatt, A.A. Members of the American Institute of Architects